

TO: MAYOR AND CITY COUNCIL

FROM: Neil Jensen, City Administrator

SUBJECT: Pool Caulking Project

MEETING DATE: May 16, 2023

BACKGROUND

The Park Board recommend approval of another portion of the swimming pool concrete area to be caulked. This keeps water from entering under the concrete and expanding in the winter. The cost of this section is \$4,950 as highlighted in the attached quote.

STAFF RECOMMENDATION

Please approve the caulking quote from the Caulkers Company Inc. for \$4,950 as outlined in the quote.

REQUESTED COUNCIL ACTION

Please make a motion to approve the caulking quote from the Caulkers Company Inc. for \$4,950 as outlined in the quote.



A State Certified Woman Owner Business

PROPOSAL/CONTRACT TERMS

BID DATE: Thursday, April 13, 2023
JOB NAME: Canon Falls Community Pool
ADDRESS: Northwest Court, Canon Falls, MN

BID SUBMITTED TO: Tony Haan
COMPANY: City of Cannon Falls
ADDRESS: 918 River Road, Cannon Falls, MN 55009
PHONE: 507-291-0457 Cell OFFICE: 507-263-4626
EMAIL: thaan@cannonfallsmn.gov

BASE BID WORK:

At the pool deck field joints within the 5' wide concrete field directly around circumference of the pool edge coping, including the outer circumference joint between the newer and older concrete decks, we will cut out existing sealants, grind masonry edges, clean out and prep all joints to be caulked, install new backer rod where needed and required and install MasterSeal SL2 Sealant and tool to a level and professional finish. **PRECAST GRAY**.....\$3,970.00

At the large, wide, existing caulked joints in the older concrete, running from the newer concrete circumference 5' band referenced above, to the outer edge of the pool deck, we will cut out existing sealants, grind masonry edges, clean out and prep all joints to be caulked, install new backer rod where needed and required and install MasterSeal SL2 Sealant and tool to a level and professional finish. **PRECAST GRAY**.....\$4,950.00

SPLASH PAD WORK:

In the Splash Pad enclosure, at all the existing caulked joints, the 2 splash area perimeter joints and center expansion joint and the surrounding concrete deck joints, we will cut out existing sealants, grind masonry edges, clean out and prep all joints to be caulked, install new backer rod where needed and required and install MasterSeal SL2 Sealant and tool to a level and professional finish. **PRECAST GRAY**.....\$3,900.00

EXCLUSIONS:

Any and all scope of work not specifically named and identified in the "Base Bid Work" narrative were not considerations in this proposal and are therefore to be Exclusions. Any scope of work beyond those identified in the Base Bid Narrative can be requested and contracted for an additional consideration and agreement.

WE PROPOSE to furnish mobilization, labor and material as required and necessary in accordance with the above for the Sum of:.....\$12,820.00

AUTHORIZED BID SIGNATURE: *Brian J. Smith* 04/07/2023

ACCEPTANCE SIGNATURE: _____

Brian Smith brianjsmith812@gmail.com 847.343.8381
7501 Commerce Lane NE, Fridley, MN 55430
Phone: 763.574.8030 Fax: 763.574.8032 www.thecaulkersco.com